



Agenda Commentary

Item Title/ Subject: Fire Station Parking Lot & Adjacent Streets

Staff Source: City Manager, Steve Hewitt

Date: Sept 13, 2013

Background/Subject Information:

Fire Station Parking Lot Asphalt was not part of the Contractors contract, City save money working directly with Local Company. Roads adjacent to the Fire Station were on our overlay plan; however we delayed to allow the new curb/gutter construction. Fire Station is near completion, Parking Lot needs installed and rather than wait until next spring for road improvements, the adjacent blocks/streets around the facility should be completed.

Parking Lot is within our Fire Station Construction Budget.

Streets Adjacent (Avant, Hayes, & 5th Street) are part of annual Capital Improvement Fund (Streets)

Circle S has supplied 2" and 1.5" pricing for street asphalt.

Recommendation:

Staff recommends approval of Parking Lot aggregate/3" asphalt. Staff recommends 1.5" asphalt cover over the adjacent streets. Base of the streets is strong; 1.5" improves quality and can support the traffic (including fire trucks).

Fire Station: \$26,250

Streets: \$18,704 (2" \$25,704)

Price/Cost: Total \$44,954.00

(see quotes)

300 E. Commerce Rd
P.O. Box 817
Clinton, OK 73601
Phone: 580-323-0514
Fax: 580-323-5681
E-Mail: circles@htswireless.com

CIRCLE S PAVING CO., INC.

Fax

To: Randy **From:** Gary Perkins
Fax: 323-4372 **Pages:** 1
Phone: **Date:** 5/27/2013
Re: Clinton Fire Station Parking **CC:**
Pricing 3" of asphalt and 3" of aggregate base

Urgent **For Review** **Please Comment** **Please Reply** **Please Recycle**

1444 Sq Yds of parking

1/2" Crusher Run (laid)	250 tons	@ \$35.00 per ton	\$ 8,750.00
S4.64-22 Asphalt (laid)	250 tons	@ \$70.00 per ton	\$17,500.00
		Total	\$26,250.00

Thanks
Gary Perkins

PHONE 580/323-0514
FAX 580/323-5681

P.O. BOX 817

CIRCLE S PAVING COMPANY, INC.

ASPHALT MATERIAL • ASPHALT PAVING
CLINTON, OKLAHOMA 73601

DATE: 7-3-13
NAME: City of Clinton
MAIL ADDRESS: _____
CITY: Clinton
PHONE: _____

CONTACT: _____
Streets Around New
Fire Station

ESTIMATE:
MATERIAL: Super C Asphalt
DEPTH: 2"
NO. SQ. YARDS: _____
NO. TONS: 378⁰⁰
AMT. PER SQ. YARD: \$ _____
AMT. PER TON: \$ 68⁰⁰
TOTAL ASPHALT: \$ 25704⁰⁰

ESTIMATE:
MATERIAL: _____
DEPTH: _____
NO. SQ. YARDS: _____
NO. TONS: _____
AMT. PER SQ. YARD: \$ _____
AMT. PER TON: \$ _____
TOTAL ASPHALT: \$ _____

CURB WORK:
LIN FEET: _____
AMT. PER FOOT: \$ _____
DIRT WORK: \$ _____
OTHER: \$ _____
TOTAL ESTIMATE: \$ _____

Avant 4th to 5th 960 yds
5th Avant to Hayes 1630 yds
Hayes 4th to 5th 800 yds
3440 yds 2" 378 TONS

ESTIMATED START DATE: _____

SIGNED: _____

DESCRIPTION: 1.5" cuts off \$7,000.00

