



Agenda Commentary

Item Title/ Subject: Annual Street Overlay Bids

Staff Source: City Manager, Steve Hewitt

Date: April 11, 2014

Background/Subject Information:

Circle S has provided bid for multiple streets. (see bid attached) Budgeted \$200,000

Recommendation:

Staff recommends the listed bids from Circle S, pulling Trenton Street (bid \$81,000) from the list and placing it on next year's top priority review.

The \$5024.00 remaining in the budget will fund a voice activated crossing at Gary and 10th Street that will help the visual impaired and youth who cross that busy intersection.

Price/Cost: \$194,976.00 Street Overlays


STREET RESURFACING REVIEW

FOR

THE CITY OF CLINTON OKLAHOMA

FEBRUARY 25, 2014

PREPARED BY:



114 North Custer
Weatherford, OK 73096
joe@ridleyllc.com
(580) 695-0118

Introduction

Ridley Engineering Group, LLC was retained to perform a review of the proposed resurfacing program for the City of Clinton Oklahoma. Mr. Joe M. Ridley, P.E. performed our review, and prepared this report.

A visual inspection was used to evaluate each section of roadway. There were no tests performed or samples taken. Quantities and dimensions were not checked or calculated and estimates were not made. Our report was based on the information available to us at this time. Should additional information become available, we reserve the right to determine the impact, if any, the new information may have on our opinions and conclusions, and to revise our opinions and conclusions if necessary and warranted.

Proposed Street Overlay 2014

Street	Existing Material	Condition	Comment
5th - Nowahy - Dougherty	Concrete	Moderate Rough	Overlay will improve ride and seal road
Regency	Asphalt	Large cracks Base good	Treat cracks prior to overlay
13th - Modelle to Jaycee	North 1/2 - Asph./Conc. South 1/2 - Asphalt	Severe to moderate cracks on N 1/2	Overlay will improve ride and seal road
13th - Gary to Nowahy	Concrete partially overlaid with asphalt	Moderate Rough	Overlay will improve ride and seal road
Terrace - 4th to 6th	Asphalt	Good	May be premature to overlay
24th - Modelle to Hayes	Concrete	Moderate	Base failures N. end and middle
Dunn - 5th to 6th	Concrete	Poor	Base failures
Trenton	Asphalt	Large Cracks Base good	Treat cracks prior to overlay
Riverview	Asphalt	Alligator Cracks	Base may need repaired

BID FORM
TYPE C ASPHALT OVERLAY
Overlay 2" Asphalt

Clinton City Streets Overlay for 2014	Width	Length	
Dunn from 5 th to 6 th	24	330	<u>6984⁰⁰</u>
13 th from Modelle to Jaycee	32	1282	<u>36072⁰⁰</u>
13 th from Gary to Nowahy	36	1397	<u>44208⁰⁰</u>
5 th from Nowahy to Dougherty	26	590	<u>12744⁰⁰</u>
Regency	28	2637	<u>64944⁰⁰</u>
Riverview	28	150	<u>3672⁰⁰</u>
24 th from Modelle to Hayes	24	1250	<u>26352⁰⁰</u>
Trenton	44	2092	<u>81000⁰⁰ *</u>
Total			<u>\$ 275,976⁰⁰</u>